



**AALBORG UNIVERSITY**  
DENMARK

**Aalborg Universitet**

## **Extensive renovation the pathology of heritage building**

Rasmussen, Torben Valdbjørn

*Published in:*  
ISBP2015 1st International Symposium on Building Pathology

*Publication date:*  
2015

*Document Version*  
Early version, also known as pre-print

[Link to publication from Aalborg University](#)

*Citation for published version (APA):*  
Rasmussen, T. V. (2015). Extensive renovation the pathology of heritage building. In V. Peixoto de Freitas (Ed.), *ISBP2015 1st International Symposium on Building Pathology: Book of Abstracts* (pp. 112). FEUP Faculty of Engineering and Management of the University of Porto.

### **General rights**

Copyright and moral rights for the publications made accessible in the public portal are retained by the authors and/or other copyright owners and it is a condition of accessing publications that users recognise and abide by the legal requirements associated with these rights.

- ? Users may download and print one copy of any publication from the public portal for the purpose of private study or research.
- ? You may not further distribute the material or use it for any profit-making activity or commercial gain
- ? You may freely distribute the URL identifying the publication in the public portal ?

### **Take down policy**

If you believe that this document breaches copyright please contact us at [vbn@aub.aau.dk](mailto:vbn@aub.aau.dk) providing details, and we will remove access to the work immediately and investigate your claim.

## Extensive renovation the pathology of heritage buildings

Torben Valdbjørn Rasmussen <sup>1</sup>

T 8

### ABSTRACT

The pathology of heritage buildings is often related to renovation initiatives typically initiated by implementing energy savings measures. But how much energy can be saved carrying out an extensive energy upgrading of a heritage complex or individual heritage buildings.

To quantify how great a potential heritage buildings possess, the extensive energy upgrading of a listed complex was followed.

The paper identifies feasible energy-upgrading measures for implementation and calculated energy savings as well as the reduction of CO<sub>2</sub> emissions. Measures are found to create synergy between the interests in preserving heritage values and the development of affordable renovation that is compatible with the requirements for the future use of the complex. The listed complex consists of four individual listed buildings. The buildings form a single complex surrounding a courtyard, see Fig. 1.

The renovation and energy upgrading of the listed complex, have shown that the primary planning including the function of a heritage building is crucial to the gained energy and CO<sub>2</sub> savings. If service facilities like a canteen or meeting facilities is needed the location of such facilities are important. These facilities can initiate the need for a significant cooling load that might influence the expected savings in CO<sub>2</sub> emissions negatively.



Figure 1. Google maps, photo showing the plan of the listed complex

**KEYWORDS:** Extensive renovation, Energy upgrading, Climate mitigation, Heritage buildings, Case study.

## Implementing BIM on rehabilitation projects for improved Preparation and production management

João Parreira <sup>1</sup>

José Costa <sup>2</sup>

José Clemente <sup>3</sup>

T 8

### ABSTRACT

The inclusion of Building Information Modelling (BIM) in construction companies strategy is becoming crucial, especially in a time when major changes in legislation towards the general use of BIM, are expected in the near future. Although BIM implementation is becoming more common, it is mainly used in new construction projects.

This paper aims to demonstrate the use of BIM technology in a rehabilitation project, a features and capabilities may replace and improve traditional methods of operations in construction companies dedicated to the rehabilitation sector.

The case study selected was the job "Renewal of S. Francisco Convent", located in Évora, 12 months' duration work with an estimated cost of 3.36 Million Euros. BIM methodology in the work preparation and development of the construction phase. This was accomplished through the 3D Modelling of all disciplines (architecture, structure, special systems), including the conditions, design compatibility and clash detection, errors and omissions analyses, coordination and subcontractors and the as-built model for facility management.

BIM implementation resulted in significant efficiency gains, characterized by a 31% to 91% on time spent in key operational processes namely work preparation, conflict detection and planning and coordination. It also confirmed an improvement in quality and consistency of design information, reducing economic impact of costs associated with schedule delays caused by field errors.

**KEYWORDS:** BIM, BIM implementation, Rehabilitation construction project, Design com